## 20 Gloucester St.

Electric Vehicle (EV) Charging Station Installation

Residential Application: 18.376 BB

Michael Gray


Three deeded parking places off Public Alley #428 belong to three of the owners at 20 Gloucester St. First parking spot on left to get EV.



Deeded parking space

20 Gloucester St., Sept. 10, 2017

Installation will take advantage of existing electrical wiring that exits building rear.



20 Gloucester St. Sept. 10, 2017

A 30' long trench, 18" deep will be dug into the asphalt to bury the new electrical line connecting building power supply to the charging station. Charging station to be on left, inside the brick column

Location of charging station

Deeded parking space



Existing electrical line

20 Gloucester St., Sept. 10, 2017


The charging station will not be attached to the brick wall. No work will be done on the 20 Gloucester building or facade during charging station installation.



Location of charging station

20 Gloucester St., Sept. 10, 2017

The electrical wires will be buried and the charging pedestal tucked against the wall.



20 Gloucester St., Sept. 16, 2017

Sep. 17, 2017 20 Gloucester Street Boston, MA 02115



Dimensions of Pedestal L: 51" W: 14" D: 8.25"





- Description
- Specifications
- Reviews:(0)
- Downloads (1)

# CLIPPERCREEK

RELIABLE. POWERFUL. MADE IN AMERICA.

## **TESLA® Wall Connector Pedestal**

- Product Code: 0300-00-022
- Availability: In Stock
- .\$659.00



Sep. 17, 2017 20 Gloucester Street Boston, MA 02115



# WALL CONNECTOR, 80A SINGLE PHASE INSTALLATION MANUAL

Approved Markets: North America, Japan, Taiwan, South Korea

For additional languages, please visit: www.tesla.com/wallconnector

## Design and installation from Tesla, with MA licensed electrician.

INSTALLATION I	NOTES_				
PARTS	S FOR PO PURCHASE (NOT OCCURRING IN	GREAT PLAINS)			
QTY	MANUFACTURERS PART NUMBER AND DESCRIPTION				
			-		
• •					
* *			-		
AHJ SPECIFICS:		DESIGNER NOTES:		INSTALLATION SPECIFICS:	
REQUIRED FOR ELECTRICAL CREATE AN ARCING/ EXPI FROM THE CENTER OF THI CENTER OF THE ELECTRIC WHEN INSTALLING SC YAR ELECTRICAL LICENSE # MF PER 237 CMR 18.01(2) M THIS ARRIVE. THIS CAN BI SUCH AS A P-TOUCH LAI USE PVC WHEN WE ARE V  -4% OF UTILITY'S PEAK L -5% OF UTILITY'S PEAK L NEW BILL IS CURRENTLY E	RD SIGNS THE SC CORPORATE R1136 SHALL BE ADDED TO THE SIGN GL UNTIL THE MODIFIED SIGNS INCLUDING E DONE WITH AN APPROPRIATE MEANS	Conduit Run: Trenching required —conduit will run to exterio —from there 30' trench thr	ker directly to bussing of new r from basement bugh hardscape	SAFETY CONCERNS:	
	DIS NUMBER: JB—100014 00	MICHAEL GRAY	DESCRIPTION: Michael Gray RESIDENC		TESLA
	K 000.02S	20 GLOUCESTER ST BOSTON, MA 02115	EV CHARGING STATION		
THE SALE AND USE OF THE RESPECTIVE	MERTER:		PAGE NAME:	энет: всу: рите: 2_Inst бИсаtion Notse,4s∠36077	1
PERMISSION OF TESTA INC.			INSTALLATION NOTES	∠_injistokuationivoteysi∠2koo17	<u> </u>

#### SAFETY PLAN

#### **INSTRUCTIONS:**

- SAFETY PLANS MUST BE MARKED BEFORE JOB
- DOCUMENT ALL ADDITIONAL HAZARDS ON THIS PAGE & MAKE NOTES ON THE JCO SHEET

NEAREST HOSPITAL OR OCCUPATIONAL/INDUSTRIAL CLINIC

NAME\_ PHONE\_

OF THE SAFETY PLAN AND SIGN INDICATING THAT THEY ARE AWARE OF THE HAZARDS ON-SITE AND THE PLAN FOR WORKING SAFELY.

NAME

FALL COMPETENT

ELECTRICAL QUALIFIED


DATE:\_\_\_\_\_

TIME: \_\_\_\_

SELECT ELECTRICAL TIE IN METHOD

MAIN / SUB

BREAKER/TAP





#### MARK UP KEY

- P PERMANENT ANCHOR
- (T) TEMPORARY ANCHOR
- DELINEATOR FOR WARNING LINE (LOW-SLOPE ROOF ONLY)
- GUARD RAIL STANCHION
- (LOW-SLOPE ROOF ONLY)
- INSTALLER LADDER
- AL AUDITOR LADDER
- JUNCTION/COMBINER BOX
- S STUBOUT
- SKYLIGHT
  - NO LADDER ACCESS (STEEP GRADE OR GROUND LEVEL OBSTRUCTIONS)
- RESTRICTED AREA
  (SOLARCITY EMPLOYEES ONLY) RESTRICTED AREA
  - CONDUIT
- (Gas) GAS SHUTOFF
- (H20) WATER SHUTOFF
- (7) SERVICE DROP
- (Z) POWER LINES

CONFIDENTIAL - THE INFORMATION HEREIN
CONTAINED SHALL NOT BE USED FOR THE
BENEFIT OF ANYONE EXCEPT TESLA INC., N
SHALL IT BE DISCLOSED IN WHOLE OR IN
PART TO OTHERS OUTSIDE THE RECIPIENT'S
ORGANIZATION, EXCEPT IN CONNECTION WITH
THE SALE AND USE OF THE RESPECTIVE
TESLA EQUIPMENT, WITHOUT THE WRITTEN
DEDMISSION OF TEST A INC

OB NUMBER:	JB-100014	00
iounting sys *	TEM:	
IODULES:		

MICHAEL GRAY 20 GLOUCESTER ST BOSTON, MA 02115 Michael Gray RESIDENCE EV CHARGING STATION

PAGE NAME: SAFETY PLAN

TESLA \_SScretyPlan\_9/M60/2017

			This is a worksheet for on-site use as need the digital app for all jobs (including the 2)			rred/uploaded through
			ELECTRICAL TESTING		JOB PH	OTOS
			Irradiance reading must be taken in the plane of array a same time as the I $_{\rm MP}$ and P $_{\rm AC}$ measurements.	and at the	<ul> <li>Finished array photo (pullback)?</li> <li>String Diagram / Safety Plan?</li> <li>All inverter or meter labels.</li> </ul>	Take these photos with your phone.
			INVERTER #1:  SERIAL NUM:  STRING: 1 2 3  Voc IMPRICE   Power (W) PAC:  INVERTER #2:  SERIAL NUM:  STRING: 1 2 3  Voc IMPRICE   POWER (W) PAC:  INVERTER #3:	4	Picture of main disconnect in off   Worker in electrical PPE testing the All ladders set up. System used to raise modules to Fall arrester or restraint with emp. A hazard encountered that isn't n notes or mentioned in the process penetration. In process penetration. Combo / J box location / Wiring. Array wire management / ground Rafter upgrades. All electrical equipment wiring / g All electrical equipment locations All conduit, including stubout. Explain if any phe	ne system or completing tie-in roof.  loyees while in use.  loyed in the SolarWorks case  oject preplan.   ing.  rounding.  / working clearance.
			SERIAL NUM:   STRING: 1 2 3   Voc   Imp   IRRADIANCE   Power (W) P <sub>AC</sub> :	4		
			Did you walk customer through system operation?  Does customer have the gateway connected?	JOB Y/N Y/N	What and where is the grounding r	neans? Y / N
			Is grounding mechanism accessible for inspection? Was placard installed? Which ladders are required for roof access?	Y / N Y / N 12 24 36		
			Are there internal conduit runs?  Are there locked gates that need to be accessed?	Y / N Y / N		
			Did we tie into an existing subpanel?  Does as-built match approved drawings?	Y / N Y / N	Are there punch list items remainin	g? Y/N
CONFIDENTIAL — THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TESIA INC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE RECIPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH	JOB MUNEER: JB—100014 00 MOUNTING SYSTEM: MODULES:	PREMISE OWNER: MICHAEL GRAY 20 GLOUCESTER ST BOSTON, MA 02115	Michael Gray RESIDENCE EV CHARGING STATION		DESIGN:	TESLA
THE SALE AND USE OF THE RESPECTIVE TESLA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESLA INC.	INVERTER:		page name: JCO SHEET		SHEET: REV: DATE: 4_JSOSheet_0/60/2017	

#### JOB HAZARD ANALYSIS

Crew leader to fill out all sections below, hold a pre-job safety meeting with all personnel, and upload this completed document and the Safety Plan to the JCO.

#### Ladder Access

- Ladders must be non-conductive, inspected before each use.
- Extension ladders must be set up on a firm and level surface at a 4-to-1
  rise-to-run angle (or 75 degrees) and the top must be secured to the structure.
   Extension style ladders placed on uneven, lose or slippery surfaces must
  additionally have the base firmly anchored or lashed so the base will not slip
- Extension ladders must be used with walk-through devices or the ladder must extend 36" above the stepping off point.
- A-frame ladders must only be climbed with the ladder spreader bars locked in the open position; A-frame ladders shall not be climbed while in the closed position (exclosed and used while leaned and part a structure).
- position (ex, closed and used while leaned against a structure).

   Additional Notes:

#### **Mobile Equipment**

- Only Qualified operators will operate equipment; operators must maintain a certification on their person for the equipment being operated.
- Type(s) of mobile equipment (type/make/model):
- Qualified operator(s):

#### Material Handling and Storage

 Materials will be staged/stored in a way that does not present a hazard to client, personnel or public. Materials stored on the roof will be physically protected from falling or sliding off.

#### Fall Protection

- A Site-specific plan for fall prevention and protection is required prior to starting work and must remain onsite at all times until work is complete; a fall rescue plan must be outlined and discussed among the crew prior to work start.
- The Competent Person is required to be onsite at all times while work at heights is ongoing.
- First-Person-Up (FPU) must install their anchor and connect before any other task, including installing other anchors. The Last-Person-Down (LPD) must be the only person on a roof uninstalling fall protection.
- FPCP (name and title):
- FPU and LPD (name and title):

#### **Electrical Safety**

- The Electrical Qualified Person (EQP) is required onsite to perform electrical work.
- All electrical work will be performed with equipment in an electrically safe condition (de-energized) unless approval has been granted prior to work start.
- Service drops and overhead electrical hazards will be identified and protected from contact, as necessary.
- EOP (name and title):

#### Public Protection Weather and Environment

- The safety of the Client and the Public must be maintained at all times.
- The Client and the Public shall be prevented from entering the work zone through the use of barriers and/or signage, as required.
- Company, Client and Public property shall be protected from falling objects.
- Pets (including dogs) shall be secured by their owners prior to work start.
- The client should not leave pets, family members, or others in charge or care of Employees, Contractors, or Temporary Workers.
- Crew leader responsible for communication with the client:
- Pets barricaded away from work areas (N/A, Yes, No):
- Client and public is excluded from work area by barricades (N/A, Yes, No):

#### Training And Pre-Job Safety Briefing

All employees onsite shall be made aware of the specific hazards
of this project and review this JHA during a pre-job briefing, and
their signature indicates awareness of site conditions and the plan
to eliminate any hazards identified prior to and during the project.

•	Crew Leader (name/title):
•	Crew Member (name/title):

#### Airborne Contaminants:

- Asbestos-containing (Transite) piping (ACP) Do not disturb (move, drill, cut, fracture, etc.)
- Asbestos-containing exterior building siding (ACS) Only Asbestos
  Class III trained personnel can drill or cut into ACS material, and
  only for purposes of mounting BOS equipment; a completed
  Asbestos Work Permit is required onsite at all times prior to
  working with ACS.
- Asbestos-containing thermal insulation (ACI) and Asbestos-containing duct wrapping (ACW) - do not disturb; no attic or crawlspace access is allowed if work to be performed could cause exposure to personnel, client or public.
- Is work around ABC or ABC containing materials being conducted (N/A, Yes, No):
- If yes, list specific tasks and protection in place:

#### <u>Restroom F.</u>

### The site supervisor shall forecast the weather conditions at the job site, prior to crew arrival, in order to mitigate any hazards

- associated with inclement weather (heat, cold, wind, rain, etc.).

  The site supervisor will utilize a portable wind meter (anemoneter) to verify actual onsite wind conditions, by checking speed at the ground and on any elevated work surface (ex, rooftop) prior to work start, at midday and prior to solar panel stacing on a roof.
- Elevated work involving the moving or maneuvering of solar panels shall cease at 25mph (sustained wind), until wind subsides.
- Forecasted weather maximum temp (degrees F):
- Measured wind speed (MPH ground):
- Measured wind speed (MPH roof):

#### Heat Related Illness Prevention

- Employees shall have access to potable drinking water that is fresh, pure, and suitably cool. The water shall be located as close as practicable to the areas where employees are working. Water shall be supplied in sufficient quantity at the beginning of the work shit to provide at least one quart per employee per hour for drinking for the entire shift. Employees may begin the shift with smaller quantities of water if they identify the location and have effective means for replenishment during the shift to allow employees to drink one quart or more per hour. The frequent drinking of water shall be encouraged.
- Shade shall be present when temperature exceeds 80 degrees
  Fahrenheit. When the outdoor temperature in the work exceeds
  80 degrees Fahrenheit, employees shall have and maintain one or
  more areas with shade at all times.
- New employees must be acclimatized. New employees will be monitored by their Crew Leader (site supervisor) for the first two (2) weeks of employment or longer when necessary.
- Employees will be allowed and encouraged to implement scheduled breaks during each shift. Employees must take cool-down breaks in the shade any time they feel the need to do so to protect them from overheating. Supervisors are REQUIRED to allow employees any break period they need during high heat conditions.
- Cool Vests are encouraged for all employees at all times during periods of high heat.
- Identify the location of the closest Occupational/Industrial Clinic or Hospital in case a crew member becomes ill.

What is the specific plan to provide and replenish sufficient water for all employees onsite?

- If offsite replenish is necessary, where will you go to replenish water (location/address):
- Who will replenish the drinking water (name):

#### Restroom Facilities

- Employees shall have access to restroom facilities with hand-washing stations. Use of onsite restroom is at the client's discretion (location is noted below). If client close not give permission, location of suitable restroom facilities with hand-washing stations at an offsite will be provided. The onsite supervisor will identify location and make arrangements to ensure all employees have access at any point.
- Restroom facilities will be (circle one): Onsite Offsite
- If offsite, add location name and address:

#### **Incident Reporting Procedure**

- ✓ Contact your Site Supervisor
  - o Name:
- o Phone:
- ✓ Contact your Manger
  - o Name:
- o Phone:
- ✓ Contact the Incident Hotline
  - o (650) 963-5678 Follow the voice prompts and provide us with:

Your full name, phone number, office location, brief description of what happened and when.

#### NOTE ADDITIONAL HAZARDS NOT ADDRESSED ABOVE

(add as many as necessray by using additional sheets):

Define the hazard:	Method/steps to prevent incident:
Define the hazard:	Method/steps to prevent incident:
Define the hazard:	Method/steps to prevent incident:
Define the hazard:	Method/steps to prevent incident:


CONFIDENTIAL — THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT ITSLA INC., NO SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSIDE THE REOPIENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPECTIVE TESIA EQUIPMENT, WITHOUT THE WRITTEN PERMISSION OF TESIA INC.


	JOB NUMBER: JB—100014 00	PREMISE OWNER: MICHAFI GRAY
R	MOUNTING SYSTEM: *	20 GLOUCESTER ST
	MODULES:	BOSTON, MA 02115
	INVERTER:	

Michael Gray RESIDENCE EV CHARGING STATION

PAGE NAME: JHA SHEET

DESIGN:	
*	T=5LF
SHEET: REV: DATE:	
4 <u>SQ</u> HAShee <b>9</b> /6/2017	





(N)200A MAIN SERVICE PANEL (N)200A MAIN BREAKER

### Wall Connector Setting: C

-(1)Tesla # 1050067-01-E Wall Connector; Variable current up to 80A, NEMA 3R, 208V or 240V, 24' Cable -(1)CUTLER-HAMMER # BR290 Breaker; 90A/2P, 2 Spaces

- (1) Eaton # BRLWCS Breaker Handle Lock Kit, Type BR -(1) AWG #3, THWN-2, Black

-(1) AWG #3, THWN-2, Red

-(1) AWG #8, THWN-2, Green EGC

- (1) CONDUIT KIT 1" x 10' EMT Conduit

CONFIDENTIAL — THE INFORMATION HEREIN CONTAINED SHALL NOT BE USED FOR THE BENEFIT OF ANYONE EXCEPT TEXA NC., NOR SHALL IT BE DISCLOSED IN WHOLE OR IN PART TO OTHERS OUTSOE THE RECIPENT'S ORGANIZATION, EXCEPT IN CONNECTION WITH THE SALE AND USE OF THE RESPICE OF THE SALE AND USE OF THE RESPICE OF THE PERMISSION OF TEXA NC.

JOB NUMBER: JR—100014 00	PREMISE UNIVERS
MOUNTING SYSTEM:	MICHAEL GRAY 20 GLOUCESTER ST
MODULES:	BOSTON, MA 02115
INVERTER:	

DESCRIP	TION:		
Mic	hael	Grav	RESIDENCE
			STATION

TUDEE LINE DIACON	
THREE LINE DIAGRA	V

DESIGN:	
*	T = 5   F
	. – – – .
SHEET: REV: DATE:	
PV 6 9/6/2017	