



# EVERSOURCE ENERGY

## NORTH WASHINGTON STREET BRIDGE 115-kV CABLE REPLACEMENT

### BOSTON, MASSACHUSETTS



LOCATION MAP  
N.T.S.




VICINITY MAP  
N.T.S.

### UNDERGROUND TRANSMISSION LINE CONSTRUCTION CONTRACT DRAWINGS

JULY 2021

129460



**ISSUED  
FOR CONSTRUCTION**



9400 WARD PARKWAY  
KANSAS CITY, MO 64114  
816-333-9400  
LICENSEE NO. 000165

REVISIONS DURING CONSTRUCTION				
NO.	DATE	DESCRIPTION	BY	CHKD.
0	07/2021	ISSUED FOR CONSTRUCTION	JAS	MJD

7/2/2021 1:39 PM - jeschatz - \\pmc\vis\Clients\IND\NCS\129460\_MassStBridge\_Design\Underground\CADD\Working\03\_GeneralNotes.dwg - PG01

DRAWING LIST TABLE	
DRAWING NUMBER	DRAWING TITLE
00	COVER SHEET
PG01	GENERAL NOTES
PG02	SHEET LAYOUT AND PROJECT OVERVIEW
PG03	PLAN AND PROFILE
PG04	PLAN AND PROFILE
PG05	PLAN AND PROFILE
PG06	PLAN AND PROFILE
PG07	DUCT BANK SECTIONS 1 OF 2
PG08	DUCT BANK SECTIONS 2 OF 2
PG09	TYPICAL DUCT BANK DETAILS
PG10	NORTH VAULT CIRCUIT 250-517 DETAILS
PG11	NORTH VAULT CIRCUIT 250-516 DETAILS
PG12	SOUTH VAULT CIRCUIT 250-517 DETAILS
PG13	SOUTH VAULT CIRCUIT 250-516 DETAILS
PG14	TYPICAL VAULT DETAILS 1 OF 5
PG15	VAULT DETAILS NORTH CIRCUIT 250-517 2 OF 5
PG16	VAULT DETAILS NORTH CIRCUIT 250-516 3 OF 5
PG17	VAULT DETAILS SOUTH CIRCUIT 250-517 4 OF 5
PG18	VAULT DETAILS SOUTH CIRCUIT 250-516 5 OF 5
PG19	FREEZE PIT DETAILS
PG20	BONDING DIAGRAM
PG21	BRIDGE PLAN SHEET 1 OF 4
PG22	BRIDGE PLAN SHEET 2 OF 4
PG23	BRIDGE PLAN SHEET 3 OF 4
PG24	BRIDGE PLAN SHEET 4 OF 4
PG25	BRIDGE PROFILE SHEET
PG26	BRIDGE DETAIL SHEET 1 OF 5
PG27	BRIDGE DETAIL SHEET 2 OF 5
PG28	BRIDGE DETAIL SHEET 3 OF 5
PG29	BRIDGE DETAIL SHEET 4 OF 5
PG30	BRIDGE DETAIL SHEET 5 OF 5
PG31	REMOVAL PLAN

CURVE TABLE							
CURVE NO.	RADIUS	CURVE LENGTH	TANGENT LENGTH	DEFLECTION ANGLE	POINT OF INTERSECTION	POINT OF CURVATURE	POINT OF TANGENCY
C1	60'	101.95'	68.24'	97.35	N 2,960,679.25, E 774,314.45	N 2,960,734.47, E 774,354.55	N 2,960,646.55, E 774,374.34
C2	100'	20.68'	10.38'	11.85	N 2,960,629.83, E 774,404.97	N 2,960,634.80, E 774,395.86	N 2,960,623.09, E 774,412.87
C3	100'	19.94'	10.00'	11.42	N 2,960,616.60, E 774,420.47	N 2,960,623.09, E 774,412.87	N 2,960,611.74, E 774,429.22
C4	40'	10.47'	5.27'	15.00	N 2,960,574.86, E 774,495.59	N 2,960,577.42, E 774,490.98	N 2,960,573.58, E 774,500.70
C5	40'	10.47'	5.27'	15.00	N 2,960,571.66, E 774,508.37	N 2,960,572.93, E 774,503.26	N 2,960,569.10, E 774,512.98
C6	50'	17.09'	8.63'	19.58	N 2,960,535.88, E 774,572.76	N 2,960,540.07, E 774,565.22	N 2,960,534.46, E 774,581.27
C7	50'	37.30'	19.57'	42.74	N 2,960,531.23, E 774,600.57	N 2,960,534.46, E 774,581.27	N 2,960,515.77, E 774,612.56
C8	50'	30.38'	15.67'	34.81	N 2,960,503.38, E 774,622.16	N 2,960,515.77, E 774,612.56	N 2,960,498.69, E 774,637.11
C9	50'	10.60'	5.32'	12.15	N 2,960,488.83, E 774,668.57	N 2,960,490.42, E 774,663.50	N 2,960,488.34, E 774,673.87
C10	50'	35.18'	18.35'	40.31	N 2,960,486.65, E 774,692.14	N 2,960,488.34, E 774,673.87	N 2,960,473.55, E 774,704.99
C11	25'	24.38'	13.26'	55.89	N 2,959,210.21, E 775,402.54	N 2,959,221.93, E 775,396.34	N 2,959,198.50, E 775,396.31
C12	30'	29.68'	16.18'	56.69	N 2,959,184.21, E 775,388.71	N 2,959,198.50, E 775,396.31	N 2,959,170.02, E 775,396.48
C13	100'	41.89'	21.26'	24.00	N 2,959,067.48, E 775,452.58	N 2,959,086.13, E 775,442.37	N 2,959,046.30, E 775,454.31
C14	30'	30.82'	16.93'	58.87	N 2,959,011.36, E 775,457.17	N 2,959,028.23, E 775,455.79	N 2,959,001.45, E 775,443.44
C15	50'	5.93'	2.97'	6.80	N 2,960,582.49, E 774,497.66	N 2,960,583.95, E 774,495.07	N 2,960,580.74, E 774,500.06
C16	50'	9.27'	4.65'	10.63	N 2,960,567.21, E 774,516.37	N 2,960,570.18, E 774,512.79	N 2,960,564.95, E 774,520.43
C17	50'	33.61'	17.47'	38.52	N 2,959,153.61, E 775,386.50	N 2,959,170.78, E 775,389.72	N 2,959,138.17, E 775,394.67

SURVEY INFORMATION:

- EXISTING UTILITIES AND SITE FEATURES SHOWN ARE BASED ON SURVEY PROVIDED BY EVERSOURCE ON 12/16/2020 AND 1/19/2021. SURVEY WAS COMPLETED BY DGT ASSOCIATES SURVEYING & ENGINEERING, IN BOSTON MASSACHUSETTS, SUFFOLK COUNTY, BOSTON PROPER DISTRICT. PROJECT NO. S-1500.00
- THE HORIZONTAL AND VERTICAL VALUES DEPICTED ARE BASED ON NAD83 MASSACHUSETTS STATE PLANE ZONE AND NAVD 1988 DATUMS.
- CONTRACTOR TO FIELD VERIFY EXISTING CONDITIONS AND FIELD LOCATE EXISTING UTILITIES PRIOR TO INSTALLATION OF PROPOSED WORK.
- QUALITY LEVEL A TEST PIT SURVEY INVESTIGATIONS AND RESULTS AS DEPICTED ON THESE DRAWINGS WERE COMPLETED BY SOFTDIG UNDERGROUND SERVICES, INC. QUALITY LEVEL A RESULTS WERE PROVIDED ON JUNE 28TH, 2021.

GENERAL NOTES:

- VERTICAL RADII SHALL BE 200' UNLESS OTHERWISE NOTED. CONTRACTOR SHALL NOT DEVIATE FROM STATED RADII WITHOUT ENGINEER APPROVAL.
- DUCT BANK SHALL MAINTAIN A TYPICAL COVER DEPTH OF 2'-6" UNLESS OTHERWISE SHOWN ON DRAWINGS. MAINTAIN 2'-0" TYPICAL VERTICAL CLEARANCE OVER OR UNDER EXISTING UTILITIES AND MAINTAIN 2'-0" TYPICAL HORIZONTAL CLEARANCE FOR ADJACENT EXISTING UTILITIES SHOWN ON DRAWINGS UNLESS OTHERWISE NOTED.
- STATIONING INDICATED IS AT CENTERLINE OF DUCT BANK SECTIONS, EXCEPT FOR WAREHOUSE/BRIDGE ATTACHMENT SECTION. SEE BRIDGE DETAILS FOR LOCATION OF ALIGNMENT ON DUCT BANK SECTION.
- CONTRACTOR SHALL PLUG CONDUIT SYSTEM WHEN WORK IS CEASED IN ACCORDANCE PER SPECIFICATIONS.
- CONTRACTOR SHALL PERFORM ALL RESTORATION WORK AS REQUIRED IN ACCORDANCE WITH SPECIFICATIONS.
- ANY DEVIATIONS FROM THE PROPOSED DUCT BANK ALIGNMENT AS SHOWN ON THE DRAWINGS SHALL REQUIRE APPROVAL FROM ENGINEER.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND CONSTRUCTION DRAWINGS. ALL WORK SHALL BE DONE IN ACCORDANCE WITH ALL APPLICABLE CODES, REGULATIONS AND REQUIREMENTS.
- ALL UNDERGROUND FACILITY ELEVATIONS & LOCATIONS SHOWN ON THE DRAWINGS ARE BASED ON THE BEST AVAILABLE INFORMATION AT THE TIME OF DESIGN. THE DEPTH OF THE UNDERGROUND UTILITIES SHOWN ON THE PROFILE OF THESE DRAWINGS ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE ACTUAL ELEVATIONS AND LOCATIONS OF ALL UNDERGROUND FACILITIES PRIOR TO CONSTRUCTION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO SURFACE OR UNDERGROUND FACILITIES WHETHER SHOWN OR NOT SHOWN ON THE DRAWINGS. CONTRACTOR SHALL HAVE THE LOCAL UTILITY LOCATING SERVICE LOCATE ALL FACILITIES BEFORE CONSTRUCTION. CALL BEFORE YOU DIG.
- SPLICE VAULT MINIMUM DEPTH OF COVER, AS MEASURED AT ANY POINT OF BURIED SPLICE VAULTS, SHALL BE 2'-6" UNLESS OTHERWISE SHOWN ON DRAWINGS.
- VAULT LOCATIONS ARE SUBJECT TO ADJUSTMENT DUE TO UNFORESEEN CONDITIONS, AND WILL REQUIRE APPROVAL FROM ENGINEER.
- NORTHING AND EASTING DESIGNATIONS FOR SPLICE VAULT LOCATIONS ARE REFERENCED TO OUTSIDE CORNERS OF SPLICE VAULT, BASED ON AN ASSUMED WIDTH OF WALLS OF 1'-0".
- ALL UTILITIES DENOTED WITH A "G" ARE GRAVITY FACILITIES WITH INTERPOLATED ELEVATIONS BASED ON SURVEY FIELD DATA. ALL OTHER UTILITIES ARE SHOWN AT DEPTHS NOTED IN GENERAL NOTES 14 AND 15.
- EXISTING UTILITIES SHOWN IN PROFILE INCORPORATE RESULTS OF TEST PITS AND MAY DIFFER FROM PLAN VIEW SURVEY, WHICH IS BASED ON UTILITIES MARKED OUT ON GROUND PRIOR TO TEST PIT EXCAVATIONS. UTILITIES DENOTED WITH "(V)" IN PROFILE HAVE BEEN VERIFIED THROUGH TEST PITS, INVERT DEPTHS IN MANHOLES/CATCH BASINS OR RECORD/DESIGN DRAWINGS.
- ASSUMED DEPTH OF GRAVITY FACILITIES WHERE INVERT INFORMATION WAS NOT AVAILABLE IS 3'-6".
- ASSUMED DEPTH OF NON-GRAVITY UTILITIES ARE:  
WATER: 4'-6"  
GAS: 3'-0"  
ELECTRIC: 3'-0"  
TELECOMMUNICATIONS: 3'-0"
- EXISTING HPFF TRANSMISSION PIPE SHALL BE DECOMMISSIONED. EXISTING PIPE AND HANGERS ATTACHED TO BRIDGES SHALL BE REMOVED. BURIED PIPE SHALL BE ABANDONED IN PLACE. CONTRACTOR TO SUBMIT PROCEDURE FOR DECOMMISSIONING AND REMOVAL WITH OWNER PRIOR TO CONSTRUCTION.
- EXISTING UTILITY PIPE WALL THICKNESS SHOWN AS PROVIDED IN SURVEY. CONTRACTOR TO FIELD VERIFY PRIOR TO DUCT BANK PLACEMENT.

115KV CABLE PULLING CALCULATIONS


CABLE PULL			TYPICAL DUCT BANK CONDUIT SIZE AND TYPE		BRIDGE/WAREHOUSE CONDUIT SIZE AND TYPE		LENGTH OF RUN IN FEET			XLPE CABLE			PULLING TENSION (in lbf)		SIDEWALL PRESSURE (in lbs/ft of radius)		APPROVED PULLING DIRECTION	
FROM	TO	CIRCUIT					VOLTAGE CLASS	SIZE	TYPE	FORWARD	REVERSED	FORWARD	REVERSED	FORWARD	REVERSED	FORWARD	REVERSE	
SOUTH TRANSITION VAULT	NORTH TRANSITION VAULT	250-517	8" SCH40 PVC	8" EPOXY FIBERGLASS	2200	115KV	5000 KCML	XLPE	25983	671	18379	580	279	FORWARD AND REVERSE				
SOUTH TRANSITION VAULT	NORTH TRANSITION VAULT	250-516	8" SCH40 PVC	8" EPOXY FIBERGLASS	1790	115KV	5000 KCML	XLPE	12556	284	9456	580	279	FORWARD AND REVERSE				

MAXIMUM ALLOWABLE PULLING TENSIONS AND SIDEWALL PRESSURES IN ACCORDANCE WITH INDUSTRY STANDARD:  
5000 kcml XLPE 115KV, 1/C: MAX PULLING TENSION = 30,000 lbf, MAX SIDEWALL PRESSURE = APPROXIMATELY 1000 lbs/ft  
COEFFICIENT OF FRICTION FOR PVC CONDUIT = 0.15  
COEFFICIENT OF FRICTION FOR EPOXY FIBERGLASS CONDUIT = 0.25  
\* INDICATES CASES EXCEEDING MAXIMUM

LEGEND

- COMMUNICATIONS: CABLE TELEVISION, ALARM OR SIGNAL LINES
- DRAIN
- ELECTRIC: ELEC. POWER LINES, CABLES, CONDUIT & LIGHTING CABLES
- COMMUNICATIONS: FIBER OPTIC
- PRODUCT: GAS, OIL, STEAM, PETROLEUM OR GASEOUS MATERIALS
- SEWER
- COMMUNICATIONS: TELEPHONE
- UNVERIFIED / UNKNOWN UTILITY TYPE
- WATER: LOW PRESSURE, HIGH PRESSURE, FIRE SERVICE

FOR NOTES REGARDING UTILITY INVESTIGATION METHODS, FINDINGS AND LIMITATIONS SEE "NORTH WASHINGTON STREET SUBSURFACE UTILITY INVESTIGATION" PLANS BY DGT ASSOCIATES PROJECT NO. S-1500.00



**ISSUED FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ  
designed M.DAGENAIS checked N.SCOTT

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

EVERSOURCE ENERGY

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
GENERAL NOTES  
BOSTON, MASSACHUSETTS




DATE	DATE	DATE	DATE
1/22/21			

BY: J.SCHATZ - BMcD, CHRIS DAGENAIS - BMcD, APP: N.SCOTT - BMcD, APP: -

PH-SCALE: N/A, V-SCALE: N/A, SIZE: D, V.S.: -

RE. PROJ. NUMBER: -

7/7/2021 1:30 PM - j.schatz - \\pmc\vis\Clients\IND\NISC\129460\_WashStBridge\_Design\Underground\CAD\Working\Sheet\_Layout.dwg - Sheet\_Layout



7-2-2021



**ISSUED  
FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ  
 designed M.DAGENAIS checked N.SCOTT





NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

## EVERSOURCE ENERGY


NORTH WASHINGTON STREET  
 BRIDGE CABLE REPLACEMENT  
 SHEET LAYOUT AND PROJECT OVERVIEW  
 BOSTON, MASSACHUSETTS

DATE	BY	DATE	BY	DATE	BY
07/02/21	J.SCHATZ - BmCd	07/02/21	M.DAGENAIS - BmCd	07/02/21	N.SCOTT - BmCd



STEEL PLATE INSTALLATION	
STATION START	STATION END
10+45	12+00

- GENERAL NOTES:**
- UTILITY TO BE REMOVED OR RELOCATED, CONTRACTOR SHALL COORDINATE WITH OWNER PRIOR TO CONSTRUCTION.
  - 6" MINIMUM VERTICAL SEPARATION SHALL BE MAINTAINED FROM CROSSING UTILITIES.
  - WHERE DUCT BANK MINIMUM DEPTH OF COVER OF 30" CANNOT BE MAINTAINED, STEEL PLATING SHALL BE INSTALLED, SEE DETAIL 8 ON PG09.
  - CONTRACTOR SHALL INSTALL 4" STEEL PIPE FROM DUCT TO TRANSITION SPLICE VAULT. SEE SECTION H ON PG08 AND DETAIL 4 ON PG16.
  - CONTRACTOR SHALL STUB (2) 2" CONDUITS FOR FUTURE USE WITH MINIMUM 15' BENDS. REFER TO SECTION I ON PG08 AND DETAIL 3 ON PG09.
  - CONTRACTOR SHALL FIELD VERIFY LOCATION PRIOR TO START OF CONSTRUCTION.
  - TUNNEL EXTERIOR SHOWN BASED ON INTERPOLATED SURVEY DATA AS PROVIDED.



**ISSUED FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ  
 designed M.DAGENAIS checked N.SCOTT

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP

**EVERSOURCE ENERGY**



TITLE: NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT PLAN & PROFILE  
 BOSTON, MASSACHUSETTS

BY: J. SCHATZ - BmCd	CHK: M.DAGENAIS - BmCd	APP: N.SCOTT - BmCd	APP: -
DATE: -	DATE: -	DATE: -	DATE: -
H-Scale: 1" = 20'	SIZE: D	FIELD BOOK & PAGES	
V-Scale: 1" = 4'	V.S.: -	R.E. DWG	
REF. PROJ. NUMBER	NISC0		PG03


NU VER: BUR\_VER  
 7/2/2021 1:39 PM - jscatz - \\pmd\vis\clients\IND\NISC\129460\_NWashStBridge\_Design\Underground\CADD\Working\PMF.dwg - North 2



STEEL PLATE INSTALLATION	
STATION START	STATION END
14+77	14+94.08



- GENERAL NOTES:**
- UTILITY TO BE REMOVED OR RELOCATED, CONTRACTOR SHALL COORDINATE WITH OWNER PRIOR TO CONSTRUCTION.
  - 6" MINIMUM VERTICAL SEPARATION SHALL BE MAINTAINED FROM CROSSING UTILITIES.
  - WHERE DUCT BANK MINIMUM DEPTH OF COVER OF 30" CANNOT BE MAINTAINED, STEEL PLATING SHALL BE INSTALLED, SEE DETAIL 8 ON PG09.
  - CONTRACTOR TO INSTALL COUPLING TO TRANSITION FROM PVC TO FIBERGLASS CONDUIT A MINIMUM OF 2'-0" FROM ABUTEMENT WALL SEE DETAIL 4 ON PG09.
  - CONTRACTOR SHALL FIELD VERIFY LOCATION PRIOR TO START OF CONSTRUCTION.



**ISSUED  
FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS  
MCDONNELL**

129460





date	JAN. 22, 2021	detailed	J. SCHATZ
designed	M.DAGENAIS	checked	N.SCOTT

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-


**EVERSOURCE  
ENERGY**

NORTH WASHINGTON STREET  
 BRIDGE CABLE REPLACEMENT  
 PLAN & PROFILE  
 BOSTON, MASSACHUSETTS

BY: J. SCHATZ - Bmcd	CHK: M.DAGENAIS - Bmcd	APP: N.SCOTT - Bmcd	APP: -
DATE	DATE	DATE	DATE
H-SCALE: 1" = 20'	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: 1" = 4'	V.S.	R.E. DWG	
REF. PROJ. NUMBER	NISC0		PG04



- GENERAL NOTES:**
- UTILITY TO BE REMOVED OR RELOCATED, CONTRACTOR SHALL COORDINATE WITH OWNER PRIOR TO CONSTRUCTION.
  - 6" MINIMUM VERTICAL SEPARATION SHALL BE MAINTAINED FROM CROSSING UTILITIES.
  - WHERE A DUCT BANK MINIMUM DEPTH OF COVER OF 30" CANNOT BE MAINTAINED, STEEL PLATING SHALL BE INSTALLED, SEE DETAIL 8 ON PG09.
  - CONTRACTOR SHALL INSTALL 4" STEEL PIPE FROM DUCT TO TRANSITION SPLICE VAULT. SEE SECTION H ON PG08 AND DETAIL 4 ON PG18.
  - CONTRACTOR TO INSTALL COUPLING TO TRANSITION FROM PVC TO FIBERGLASS CONDUIT. A MINIMUM OF 2'-0" FROM ABUTMENT WALL, SEE DETAIL 3 AND 4 ON PG 09.
  - CONTRACTOR SHALL STUB (2) 2" CONDUITS FOR FUTURE USE WITH MINIMUM 15' BENDS. REFER TO SECTION I ON PG08.



**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-






129460	
date	detailed
JAN. 22, 2021	J. SCHATZ
designed	checked
M.DAGENAIS	N.SCOTT

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-


# EVERSOURCE ENERGY

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
PLAN & PROFILE  
BOSTON, MASSACHUSETTS

BY: J.SCHATZ - BmCd	CHKD: M.DAGENAIS - BmCd	APP: N.SCOTT - BmCd	APP: -
DATE	DATE	DATE	DATE
1" = 20'	SIZE: D	FIELD BOOK & PAGES	
1" = 4'	V.S.	R.E. DWG	
REF. PROJ. NUMBER	NISC0		PG05



- GENERAL NOTES:**
- UTILITY TO BE REMOVED OR RELOCATED, CONTRACTOR SHALL COORDINATE WITH OWNER PRIOR TO CONSTRUCTION.
  - 6" MINIMUM VERTICAL SEPARATION SHALL BE MAINTAINED FROM CROSSING UTILITIES.
  - WHERE A DUCT BANK MINIMUM DEPTH OF COVER OF 30" CANNOT BE MAINTAINED, STEEL PLATING SHALL BE INSTALLED. SEE DETAIL 8 ON PG09.
  - CONTRACTOR SHALL INSTALL 4" STEEL PIPE FROM DUCT TO TRANSITION SPLICE VAULT. SEE SECTION H ON PG08.
  - CONTRACTOR SHALL STUB (2) 2" CONDUITS FOR FUTURE USE WITH MINIMUM 15' BENDS. REFER TO SECTION I ON PG08 AND DETAIL 3 ON PG09.
  - CONTRACTOR SHALL FIELD VERIFY LOCATION PRIOR TO START OF CONSTRUCTION.
  - POTENTIAL UNIDENTIFIED EXISTING UTILITY CONFLICT. CONTRACTOR TO FIELD VERIFY LOCATION PRIOR TO TRENCHING ACTIVITIES.



**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS & MCDONNELL**  
129460

date	JAN. 22, 2021	detailed	J. SCHATZ
designed	M.DAGENAIS	checked	N.SCOTT


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**


NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
PLAN & PROFILE  
BOSTON, MASSACHUSETTS

BY	J.SCHATZ - BMcD	CHKD	M.DAGENAIS - BMcD	APP	N.SCOTT - BMcD	APP	-
DATE		DATE		DATE		DATE	
H-SCALE	1" = 20'	SIZE	D	FIELD BOOK & PAGES			
V-SCALE	1" = 4'	V.S.	D	RE. DWG			
REF. PROJ. NUMBER		NSCO					PG06

NU VER: BUR\_MER




SECTION A  
NTS




SECTION B  
NTS

NOT USED


SECTION C  
NTS



SECTION D  
NTS



SECTION E  
NTS



SECTION F  
NTS

- GENERAL NOTES:**
- DUCT BANK OUTSIDE DIMENSIONS ROUNDED UP TO THE NEAREST INCH FOR CLARITY.
  - ALL CONNECTING PIPING SHALL BE SCHEDULE 80 ASTM A53 GRADE B OR ASTM A106 GRADE B CARBON STEEL.
  - ROAD AND SUBBASE THICKNESS TO BE FIELD VERIFIED ON PROJECT.
  - CONDUITS A1, B1, C1, G1, D1, S1, S2 ARE ASSOCIATED WITH CIRCUIT 250-517. CONDUITS A2, B2, C2, G2, D2, S3, S4 ARE ASSOCIATED WITH CIRCUIT 250-516.



**ISSUED FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ

designed M.DAGENAIS checked N.SCOTT

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP

**EVERSOURCE ENERGY**







TITLE NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT DUCT BANK SECTIONS 1 OF 2 BOSTON, MASSACHUSETTS

BY J.SCHATZ - BMcD	CHKD M.DAGENAIS - BMcD	APP N.SCOTT - BMcD	APP (BMcD)
DATE 01/22/21	DATE	DATE	DATE
H-SCALE N/A	SIZE D	FIELD BOOK & PAGES	
V-SCALE N/A	V.S.	R.E. DWG	
REF. PROJ. NUMBER	129460	INSD	PG07

7/27/2021 1:38 PM j.schatz - \\bmc\vis\clients\IND\NISC\129460\_MassBridges\Design\Underground\CADD\Working\05\_Sections.dwg - PG001



NU VER: BUR\_VER  
 7/2/2021 1:38 PM j.schatz - \\pmc\d\is\clients\IND\NISC\129460\_WashStBridge\Design\Underground\CADD\Working\05\_Sections.dwg - PG001 (2)



**ISSUED FOR CONSTRUCTION**

- GENERAL NOTES:**
- DUCT BANK OUTSIDE DIMENSIONS ROUNDED UP TO THE NEAREST INCH FOR CLARITY.
  - ALL CONNECTING PIPING SHALL BE SCHEDULE 80 ASTM A53 GRADE B OR ASTM A106 GRADE B CARBON STEEL.
  - ROAD AND SUBBASE THICKNESS TO BE FIELD VERIFIED ON PROJECT.
  - CONDUITS A1, B1, C1, G1, D1, S1, S2 ARE ASSOCIATED WITH CIRCUIT 250-517. CONDUITS A2, B2, C2, G2, D2, S3, S4 ARE ASSOCIATED WITH CIRCUIT 250-516.



129460  
 date JAN. 22, 2021 detailed J. SCHATZ  
 designed M.DAGENAIS checked N.SCOTT

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP

## EVERSOURCE ENERGY

NORTH WASHINGTON STREET  
 BRIDGE CABLE REPLACEMENT  
 DUCT BANK SECTIONS 2 OF 2  
 BOSTON, MASSACHUSETTS


BY: J.SCHATZ - BMcD	CHK: M.DAGENAIS - BMcD	APP: N.SCOTT - BMcD	APP: (BMcD)
DATE: 01/22/21	DATE:	DATE:	DATE:
H-SCALE: N/A	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.:	R.E. DWG	
R.E. PROJ. NUMBER: 129460		NISC	

PG08




**CONSTRUCTION JOINT DETAIL**  
**DETAIL 1**  
 NTS


**NOTE:**  
 1. 2" AND 4" DUCTS NOT SHOWN FOR CLARITY.




**TYPICAL MANDREL DETAIL**  
**DETAIL 2**  
 NTS




**TEMPORARY CONDUIT STUB OUT DETAILS**  
**DETAIL 3**  
 NTS




**REDUCING ADAPTER**  
**DETAIL 4**  
 NTS




**TYPICAL DUCT BANK WITH UTILITY CLEARANCE**  
**DETAIL 5**  
 NTS



**TYPICAL HORIZONTAL UTILITY CLEARANCE DETAIL**  
**DETAIL 6**  
 NTS




**TYPICAL PIPE SUPPORT ACROSS OPEN EXCAVATION**  
**DETAIL 7**  
 NTS



**TYPICAL STEEL PLATING**  
**DETAIL 8**  
 NTS

- GENERAL NOTES:**
- SEE DRAWING PG07 AND PG08 FOR CONDUIT SECTION.
  - 2'-0" MIN. CLEARANCE MAINTAINED UNLESS OTHERWISE NOTED ON PLAN AND PROFILE.
  - 2'-0" MAX SPAN, OR DIRECTED BY THE UTILITY WHICHEVER IS LESS.
  - CONTRACTOR SHALL SUBMIT METHOD OF SUPPORT TO RESPECTIVE UTILITY OWNERS FOR APPROVAL PRIOR TO CONSTRUCTION.
  - PROVIDE A MINIMUM OF 3'-0" OF THERMAL BACKFILL AROUND ALL SIDES OF CONDUITS.
  - WHERE A MINIMUM DEPTH OF COVER OF 30" CANNOT BE MAINTAINED, STEEL PLATTING SHALL BE REQUIRED.
  - ROAD AND SUBBASE THICKNESS TO BE FIELD VERIFIED ON PROJECT.
  - STEEL PLATES TO BE PLACED ON TOP OF EACH OTHER WITH NO TWO JOINTS OVERLAPPED. STEEL PLATE SHALL OVERHANG ENCASMENT BY NO LESS THAN 6" ON EACH SIDE.
  - REDUCING ADAPTER AS PROPOSED BY CONTRACTOR FOR REVIEW AND APPROVAL BY OWNER (DIMENSIONS SHOWN ARE NOMINAL).



**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS & MCDONNELL**

129460

date JAN. 22, 2021 detailed J. SCHATZ

designed J. SCHATZ checked CHECKER

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

TITLE: NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT TYPICAL DUCT BANK DETAILS BOSTON, MASSACHUSETTS

BY: J.SCHATZ - BMcD DATE: 01/22/21

CHKD: M.DAGENAIS - BMcD DATE: -

APP: N.SCOTT - BMcD DATE: -

APP: (BMcD) DATE: -


PI-SCALE: N/A SITE: D FIELD BOOK & PAGES

V-SCALE: N/A V.S.: - R.E. DWG

R.E. PROJ. NUMBER: 129460 NISCD

PG09

7/2/2021 1:38 PM j.schatz ... \bmc\dfs\clients\IND\NUSC\129460\_NWASHSTRIDGE\DESIGN\UNDERGROUND\CADD\WORKING\SPICE VAULT DETAILS.DWG - Splice Vault North A




ISOMETRIC VIEW


- NOTE:**
1. SPLICE VAULTS AS SHOWN BASED ON AN ASSUMED WALL THICKNESS OF 1'-0". CONTRACTOR RESPONSIBLE FOR FINAL DESIGN OF CAST-IN PLACE VAULT.
  2. CONTRACTOR TO FIELD VERIFY EXISTING PIPE TIE IN LOCATIONS PRIOR TO CONSTRUCTION.

*J. Schatz*  
 COMMONWEALTH OF MASSACHUSETTS  
**LANE PATRICK PULS**  
 CIVIL  
 No. 48318  
 REGISTERED PROFESSIONAL ENGINEER  
 7-2-2021

**ISSUED FOR CONSTRUCTION**




TRANSITION VAULT CIRCUIT 250-517  
 NORTH HPFF END WALL  
 SECTION A




ANGLE TO BE MEASURED PLUMB FROM VAULT FACE LOOKING TOWARDS TRANSITION PIPE TIE-IN LOCATION

SEGMENTS	LENGTH (FT)	RADIUS (FT)	ANGLE (DEG)	ROTATION (DEG)
1	2.00			
2		6	30	5.88
3	5.31			
4		6	30	0
5	7.57			
6		6	25	2.36
7	1.00			

TRANSITION PIPE SEGMENT TABLE



TRANSITION PIPE PROFILE VIEW  
 SECTION B



TRANSITION PIPE PLAN VIEW  
 SECTION C

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-



**BURNS & MCDONNELL**  
 129460  
 date JAN. 22, 2021 detailed J. SCHATZ  
 designed J. SCHATZ checked CHECKER

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-


**EVERSOURCE ENERGY**  
 NORTH WASHINGTON STREET  
 BRIDGE CABLE REPLACEMENT  
 NORTH VAULT CIRCUIT 250-517 DETAIL  
 BOSTON, MASSACHUSETTS

DR J. SCHATZ - BMcD	CHK M. DAGENAIS - BMcD	APP N. SCOTT - BMcD	APP (BMcD)
DATE 02/09/21	DATE	DATE	DATE
H-SCALE N/A	SIZE D	FIELD BOOK & PAGES	
V-SCALE N/A	V.S.	R.E. DWG	
R.E. PROJ. NUMBER	129460	NUSC	PG10

7/2/2021 1:38 PM j.schatz ... \\bmc\dfs\clients\IND\NUSC\129460\_NWASHSTRIDGE\DESIGN\UNDERGROUND\CADD\WORKING\SPICE VAULT DETAILS.DWG - Splice Vault North B




TRANSITION VAULT CIRCUIT 250-516 NORTH HPFF END WALL SECTION




SEGMENTS	LENGTH (FT)	RADIUS (FT)	ANGLE (DEG)	ROTATION (DEG)
1	2.00			
2		6	20	20
3	2.22			
4		6	21	20
5	2.00			

TRANSITION PIPE SEGMENT TABLE




TRANSITION PIPE PROFILE VIEW SECTION



TRANSITION PIPE PLAN VIEW SECTION

- NOTE:
1. SPLICE VAULTS AS SHOWN BASED ON AN ASSUMED WALL THICKNESS OF 1'-0". CONTRACTOR RESPONSIBLE FOR FINAL DESIGN OF CAST-IN PLACE VAULT.
  2. CONTRACTOR TO FIELD VERIFY EXISTING PIPE TIE IN LOCATIONS PRIOR TO CONSTRUCTION.



**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS & MCDONNELL**

129460

date JAN. 22, 2021 detailed J. SCHATZ

designed J. SCHATZ checked CHECKER


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

TITLE NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT NORTH VAULT CIRCUIT 250-516 DETAIL BOSTON, MASSACHUSETTS

BY J.SCHATZ - BMCd	CHKD M.DADENNAIS - BMCd	APP N.SCOTT - BMCd	APP (BMCd)
DATE 02/09/21	DATE	DATE	DATE
H-SCALE N/A	SIZE D	FIELD BOOK & PAGES	
V-SCALE N/A	V.S.	R.E. DWG	
R.E. PROJ. NUMBER	129460	NUSC	PG11

7/2/2021 1:38 PM j.schatz ... \pmsd\vis\clients\IND\NUSC\129460\_NWASHSTRIDGE\Design\Underground\CADD\Working\Splice Vault Details.dwg - Splice Vault South A




ISOMETRIC VIEW

- NOTE:**
- SPLICE VAULTS AS SHOWN BASED ON AN ASSUMED WALL THICKNESS OF 1'-0". CONTRACTOR RESPONSIBLE FOR FINAL DESIGN OF CAST-IN PLACE VAULT.
  - CONTRACTOR TO FIELD VERIFY EXISTING PIPE TIE IN LOCATIONS PRIOR TO CONSTRUCTION.


*J. Schatz*  
 COMMONWEALTH OF MASSACHUSETTS  
**LANE PATRICK PULS**  
 CIVIL  
 No. 48318  
 REGISTERED PROFESSIONAL ENGINEER  
 7-2-2021

**ISSUED FOR CONSTRUCTION**



TRANSITION VAULT CIRCUIT 250-517 SOUTH HPFF END WALL


**SECTION** A



ANGLE TO BE MEASURED PLUMB FROM VAULT FACE LOOKING TOWARDS TRANSITION PIPE TIE-IN LOCATION


SEGMENTS	LENGTH (FT)	RADIUS (FT)	ANGLE (DEG)	ROTATION (DEG)
1	2.00			
2		6	29	14
3	6.85			
4		6	30	13
5	2.00			

TRANSITION PIPE SEGMENT TABLE



TRANSITION PIPE PROFILE VIEW

**SECTION** B



TRANSITION PIPE PLAN VIEW

**SECTION** C

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
A	07/01/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS & MCDONNELL**

129460

date JAN. 22, 2021 detailed J. SCHATZ

designed J. SCHATZ checked CHECKER


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

TITLE NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT SOUTH VAULT CIRCUIT 250-517 DETAILS BOSTON, MASSACHUSETTS

BY J.SCHATZ - BMcD	CHK M.DAGENAIS - BMcD	APP N.SCOTT - BMcD	APP (BMcD)
DATE 02/09/21	DATE	DATE	DATE
H-SCALE N/A	SIZE D	FIELD BOOK & PAGES	
V-SCALE N/A	V.S.	R.E. DWG	
R.E. PROJ. NUMBER	129460	NUSC0	PG12

7/2/2021 1:38 PM j.schatz ... \bmc\dfs\clients\IND\NUSC\129460\_NWASHSTRIDGE\DESIGN\UNDERGROUND\CADD\WORKING\SPICE VAULT DETAILS.DWG - Splice Vault - South B





- NOTE:**
1. SPLICE VAULTS AS SHOWN BASED ON AN ASSUMED WALL THICKNESS OF 1'-0". CONTRACTOR RESPONSIBLE FOR FINAL DESIGN OF CAST-IN PLACE VAULT.
  2. CONTRACTOR TO FIELD VERIFY EXISTING PIPE TIE-IN LOCATIONS PRIOR TO CONSTRUCTION.

*J. Schatz*  
 7-2-2021





**ISSUED FOR CONSTRUCTION**



SEGMENTS	LENGTH (FT)	RADIUS (FT)	ANGLE (DEG)	ROTATION (DEG)
1	2.00			
2		6	30	20
3	4.96			
4		6	31	21
5	2.00			

TRANSITION PIPE SEGMENT TABLE



NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS & MCDONNELL**

129460

date JAN. 22, 2021 detailed J. SCHATZ




designed J. SCHATZ checked CHECKER

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**



TITLE NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT SOUTH VAULT CIRCUIT 250-516 DETAILS BOSTON, MASSACHUSETTS

BY J.SCHATZ - BmCd	CHK M.DAGENAIS - BmCd	APP N.SCOTT - BmCd	APP (BmCd)
DATE 02/09/21	DATE	DATE	DATE
PI-SCALE N/A	SIZE D	FIELD BOOK & PAGES	
V-SCALE N/A	V.S.	R.E. DWG	
R.E. PROJ. NUMBER	129460	NUSC	PG13





NOTE:  
CONTRACTOR SHALL ATTACH BRASS TAG 1'-6" BELOW FINISHED GRADE ON THE INSIDE OF THE CHIMNEY AND ON THE VAULT WALL OPPOSITE THE RACKING.



NOTES:  
1. CONTRACTOR SHALL ATTACH TAG 6" FROM THE CONDUIT ON EACH END WALL OF SPLICE VAULT AS SHOWN IN SECTION A WITH DELINEATION OF NEXT SPLICE VAULT IN THE CIRCUIT AND DISTANCE TO SPLICE VAULT.



NOTES:  
1. CHARACTER SHALL BE 4" HIGH BOLD TYPE.  
2. CHARACTER SHALL BE CENTERED ON SIGN.  
3. - BACKGROUND: WHITE  
- LETTERING: BLACK  
- CHARACTERS: 1, 2, & 3 AS SHOWN.



NOTES:  
1. GROUND PIGTAILS TO EXTEND A MINIMUM OF 18 INCHES FROM BOTH SIDES OF VAULT WALL PENETRATION.  
2. GROUND CLIPS MAX 1' FROM ALL MANHOLE CORNERS, AND MAX 4' OC SPACING ALONG WALLS USE 1/2" PVC COATED, MALLEABLE IRON RIGID STEEL CONDUIT 1 HOLE STRAP WITH BACKSTRAP. ALL HARDWARE AND INSERTS TO BE STAINLESS STEEL.  
3. ALL GROUND CONNECTIONS TO MANHOLE RACKS ETC. SHALL BE VIA A TINNED CU 1 HOLE.  
4. PASS GROUND CONDUCTOR THROUGH VAULT WALL AND SUPPORT ALONG VAULT WALL AS HIGH AS POSSIBLE BUT NO MORE THAN 12" DOWN FROM VAULT CEILING.  
5. BOND GROUNDS FROM EARTHING TO VAULT/DUCTBANK GROUND.  
6. CABLE VENDOR IS TO PLACE PHASE DESIGNATIONS.



**ISSUED FOR CONSTRUCTION**



129460  
date JAN. 22, 2021 detailed J. SCHATZ  
designed M.DAGENAIS checked N.SCOTT


NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

<b>EVERSOURCE ENERGY</b>					
NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT TYPICAL VAULT DETAILS 1 OF 5 BOSTON, MASSACHUSETTS					
BY J.SCHATZ - BMcD	DATE 02/09/21	CHK M.DAGENAIS - BMcD	APP N.SCOTT - BMcD	APP (BMcD)	DATE
PH-SCALE N/A	SIZE D	V-SCALE N/A	V.S.	FIELD BOOK & PAGES	R.E. DWG
REF. PROJ. NUMBER	129460	NSCD			PG14









**CIRCUIT 250-516 SPLICE VAULT DEVELOPMENT PLAN**

DETAIL 1  
NTS




WALLS FOLD UP

PULLING EYE (ACTEK MODEL AK57156 HOIST RING, 40K LB WORKING LOAD WITH A 3:1 SAFETY FACTOR) (TYP 2 PLCS)




**SPLICE VAULT PLAN VIEW**

DETAIL 2  
NTS




**ELEVATION VIEW**

SECTION A  
NTS



**MANHOLE TETHER DETAIL**

DETAIL 3  
NTS




NOTE:

1. STEEL DOWELING SHALL PENETRATE VAULT WALL A MINIMUM OF 3". STEEL SHALL OVERLAP 1'-6" AND BE TIED TOGETHER.


**4" STEEL PIPE VAULT PENETRATION**

DETAIL 4  
NTS



**SIDE ELEVATION VIEW**

SECTION B  
NTS




**SIDE ELEVATION VIEW**

SECTION C  
NTS

NOTES:

1. FERROUS REBAR WITHIN SPLICE CHAMBER WALLS SHALL NOT FORM A CLOSED LOOP AROUND ANY INDIVIDUAL 8" CONDUIT OPENING.
2. CONTRACTOR TO ADJUST TETHER SYSTEM FOR MAXIMUM COVER RISE OF 24"



**ISSUED FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ

designed M.DAGENAIS checked N.SCOTT

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-


**EVERSOURCE ENERGY**

TITLE NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT VAULT DETAILS NORTH CIRCUIT 250-516 3 OF 5 BOSTON, MASSACHUSETTS

BY	DATE	CHKD	DATE	APP	DATE	APP	DATE
J.SCHATZ - BMcD	02/09/21	M.DAGENAIS - BMcD	02/09/21	N.SCOTT - BMcD	02/09/21		



FIELD BOOK & PAGES  
R.E. DWG

REF. PROJ. NUMBER 129460 NISCO PG16




**CIRCUIT 250-517 SPLICE VAULT DEVELOPMENT PLAN**

DETAIL 1  
NTS




**MANHOLE TETHER DETAIL**

DETAIL 3  
NTS




**SPLICE VAULT PLAN VIEW**

DETAIL 2  
NTS




**SIDE ELEVATION VIEW**

SECTION B  
NTS



**SIDE ELEVATION VIEW**

SECTION C  
NTS



**ELEVATION VIEW**

SECTION A  
NTS

*Signature*  
**LANE PATRICK PULS CIVIL**  
 No. 48318  
 REGISTERED PROFESSIONAL ENGINEER  
 7-2-2021

**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

<b>BURNS &amp; MCDONNELL</b>	
129460	
date	detailed
JAN. 22, 2021	J. SCHATZ
designed	checked
M.DAGENAIS	CHECKER

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-


**EVERSOURCE ENERGY**

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
VAULT DETAILS SOUTH CIRCUIT 250-517 4 OF 5  
BOSTON, MASSACHUSETTS

BY: J.SCHATZ - BMcD	CHKD: M.DAGENAIS - BMcD	APP: N.SCOTT - BMcD	APP: (BMcD)
DATE: 02/09/21	DATE:	DATE:	DATE:
H-SCALE: N/A	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.:	R.E. DWG	
REF. PROJ. NUMBER: 129460	NSC0	PG17	


- NOTES:**
1. FERROUS REBAR WITHIN SPLICE CHAMBER WALLS SHALL NOT FORM A CLOSED LOOP AROUND ANY INDIVIDUAL 8" CONDUIT OPENING.
  2. CONTRACTOR TO ADJUST TETHER SYSTEM FOR MAXIMUM COVER RISE OF 24"

7/2/2021 1:38 PM j.schatz ... \pmsd\vis\clients\IND\NUSC\129460\_NWASHSTRIDGE\DESIGN\UNDERGROUND\CADD\WORKING\SPLICE VAULT DETAILS.DWG - Standard Vault Details South A




**CIRCUIT 250-516 SPLICE VAULT DEVELOPMENT PLAN**

DETAIL 1  
NTS




WALLS FOLD UP




**SPLICE VAULT PLAN VIEW**

DETAIL 2  
NTS




**ELEVATION VIEW**

SECTION A  
NTS



**MANHOLE TETHER DETAIL**

DETAIL 3  
NTS




NOTE:

- STEEL DOWELING SHALL PENETRATE VAULT WALL A MINIMUM OF 3". STEEL SHALL OVERLAP 1'-6" AND BE TIED TOGETHER.


**4" STEEL PIPE VAULT PENETRATION**

DETAIL 4  
NTS



**SIDE ELEVATION VIEW**

SECTION B  
NTS




**SIDE ELEVATION VIEW**

SECTION C  
NTS

NOTES:

- FERROUS REBAR WITHIN SPLICE CHAMBER WALLS SHALL NOT FORM A CLOSED LOOP AROUND ANY INDIVIDUAL 8" CONDUIT OPENING.
- CONTRACTOR TO ADJUST TETHER SYSTEM FOR MAXIMUM COVER RISE OF 24"



**ISSUED FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ

designed M.DAGENAIS checked N.SCOTT

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**


TITLE NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT VAULT DETAILS SOUTH CIRCUIT 250-516 5 OF 5 BOSTON, MASSACHUSETTS

BY	DATE	CHKD	DATE	APP	DATE	APP	DATE
J.SCHATZ - BMcD	02/09/21	M.DAGENAIS - BMcD		N.SCOTT - BMcD			


FIELD BOOK & PAGES  
R.E. DWG  
129460  
PG18



TOP VIEW



END ELEVATION VIEW



**FREEZE PIT**

DETAIL 1

NTS

- GENERAL NOTES:**
- FREEZE PIT SHOWN FOR INFORMATION ONLY. CONTRACTOR SHALL DESIGN SITE SPECIFIC FREEZE PIT.
  - COMPLETED SHED EXTERIOR TO BE COVERED WITH HEAVY GAUGE ROOFING PAPER AND PLASTIC SHEETING.
    - PROVISIONS SHALL BE TAKEN TO ENSURE INTERIOR OF SHED REMAINS WATERPROOF DURING ENTIRE PROJECT.
    - PROVISIONS SHALL BE TAKEN TO KEEP ALL GROUND AND RAIN WATER AWAY FROM FREEZE PIT.
    - PUMPS SHALL BE USED TO MAINTAIN A DRY FREEZE PIT EXCAVATION AT ALL TIMES.
  - FREEZES ARE TO BE MONITORED CONSTANTLY UNTIL RELEASED BY EVERSOURCE.
  - MINIMUM OF ONE SUMP HOLE, WITH ADDITIONAL SUMP HOLES ADDED BASED ON EXISTING CONDITIONS.
  - LOCATION OF FREEZE PIT TO BE DETERMINED BY FIELD CONDITIONS. USE CAUTION WORKING AROUND THE OTHER CIRCUIT.
  - NEAT-LINE PIPES SHOWN FOR CLARITY. ACTUAL LOCATION/ORIENTATION MAY VARY DUE TO PRESENCE OF HORIZONTAL/VERTICAL BENDS.

**REFERENCE DRAWINGS:**

- PG03, PG04, PG05 & PG06: CIRCUIT 250-516 & 250-517 PLAN & PROFILE

**ISSUED FOR CONSTRUCTION**



129460

date JAN. 22, 2021 detailed J. SCHATZ

designed M.DAGENAIS checked CHECKER

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-




NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVSOURCE ENERGY**

TITLE: NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT FREEZE PIT DETAILS  
BOSTON, MASSACHUSETTS


BY: J. SCHATZ - BMcD	CHKD: M.DAGENAIS - BMcD	APP: N.SCOTT - BMcD	APP: -
DATE: 1/22/21	DATE:	DATE:	DATE:
H-SCALE: N/A	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.:	R.E. DWG	
R.E. PROJ. NUMBER			DWG NO. PG19

7/1/2021 1:32 PM - j.schatz - \\pmsd\vis\clients\IND\NISC\129460\_MWashStBridge\_Design\Underground\CAD\Working\04\_MWash\_Bonding\_Schematic.dwg - PG01  
 NU VER: 02/2012



**NOTES:**

1. ALL LINK BOXES IN VAULTS TO HAVE VIEWING WINDOWS.
2. ALL INSULATED GROUNDING AND BONDING CABLES SHALL HAVE A MINIMUM JACKET THICKNESS OF 130 MILS.



NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

**BURNS  
MCDONNELL**

129460

date	JAN. 22, 2021	detailed	J. SCHATZ
designed	M.DAGENAIS	checked	N.SCOTT


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP

**EVERSOURCE  
ENERGY**

TITLE  
NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BONDING DIAGRAM  
BOSTON, MASSACHUSETTS

BY	J.SCHATZ - BMcD	CHKD	M.DAGENAIS - BMcD	APP	N.SCOTT - BMcD	APP	(BMcD)
DATE	01/22/21	DATE		DATE		DATE	
H-SCALE	N/A	SIZE	D	FIELD BOOK & PAGES			
V-SCALE	N/A	V.S.		R.E. DWG			
R.E. PROJ. NUMBER	129460	NISC0					

**PG20**



**NOTES:**  
SEE PG25 FOR DUCT BANK PROFILE ACROSS BRIDGES.

"D##" CORRESPONDS TO WAREHOUSE INTERMEDIATE DIAPHRAGM NUMBER ##. SEE PG26 FOR DETAILS.

"E##" CORRESPONDS TO DUCTBANK EXPANSION JOINT NUMBER ##. SEE PG26 FOR DETAILS.


ALL WAREHOUSE UTILITY SUPPORTS SHALL BE TYPE 1, EXCEPT FOR LOCATIONS MARKED C2 OR C3. LOCATIONS MARKED C2 SHALL BE TYPE 2, SEE PG26 FOR DETAILS.

LOCATIONS MARKED C3 SHALL BE ANCHOR HANGERS, TYPE 3. SEE PG29 FOR DETAILS.

INSTALL WAREHOUSE UTILITY SUPPORTS MIDWAY BETWEEN DIAPHRAGMS AS SHOWN ABOVE. MAX SPACING BETWEEN SUPPORTS AND DIAPHRAGMS =9'-6".

SEE EXISTING WAREHOUSE BRIDGE PLANS AND PROPOSED MAIN BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR FRAMING DETAILS, INCLUDING LOCATION OF UTILITY SUPPORTS AND CROSS FRAMES ON MAIN BRIDGE.

STATIONING ALONG BASELINE OF BRIDGES SHOWN FOR INFORMATION ONLY, SEE BRIDGE PLANS



This document has been digitally sealed. 07/02/2021



**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER  
designed A. FERDON checked J. DAVIS

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

TITLE: NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT BRIDGE PLAN SHEET 1 OF 4 BOSTON, MASSACHUSETTS


BY: A. FERDON - BmCd	CHKD: J.DAVIS - BmCd	APP: -	APP: -
DATE: 07/02/21	DATE: -	DATE: -	DATE: -
H-SCALE: 1" = 12'	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.: -	R.E. DWG	
R.E. PROJ. NUMBER	NISC0		PG21

7/27/2021 11:01 AM - mrfischer - Z:\Clients\TND\NUSC\129460\_MWentStBridge\Design\Underground\CA0D\Bridges\Plan\_Sheet\_2.dwg - North 1  
 NU VER: BDR\_VER



**NOTES:**

- SEE PG25 FOR DUCT BANK PROFILE ACROSS BRIDGES.
- ALL MAIN BRIDGE UTILITY SUPPORTS SHALL BE TYPE S1, EXCEPT FOR LOCATIONS MARKED S2, S3, S4, OR S5. LOCATIONS MARKED S5 SHALL BE ANCHOR HANGERS. SEE PG30 FOR DETAILS.
- "E##" CORRESPONDS TO DUCTBANK EXPANSION JOINT ##. SEE PG26 FOR DETAILS.
- INSTALL HANGER FRAMES ON MAIN BRIDGE UTILITY SUPPORTS AND CROSS FRAMES. PER MAIN BRIDGE PLANS, MAX SPACING BETWEEN UTILITY SUPPORTS AND/OR CROSS FRAMES = 9'-6".
- SEE PROPOSED MAIN BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR FRAMING DETAILS, INCLUDING LOCATION OF UTILITY SUPPORTS AND CROSS FRAMES.
- CROSS FRAMES AND UTILITY SUPPORTS ARE ONLY SHOWN IN BAY OF PROPOSED DUCTBANK, FOR CLARITY.
- CENTERLINES OF BOX GIRDER WEBS ARE SHOWN AT TOP OF WEB.
- STATIONING ALONG BASELINE OF BRIDGES SHOWN FOR INFORMATION ONLY, SEE BRIDGE PLANS.



This document has been digitally sealed. 07/02/2021



**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER  
 designed A. FERDON checked J. DAVIS

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

TITLE: NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT BRIDGE PLAN SHEET 2 OF 4 BOSTON, MASSACHUSETTS

BY: A. FERDON - BMcD	CHKD: J.DAVIS - BMcD	APP: -	APP: -
DATE: 07/02/21	DATE: -	DATE: -	DATE: -
H-SCALE: 1" = 12'	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.: -	R.E. DWG	
R.E. PROJ. NUMBER	NUSC0		PG22

7/2/2021 11:00 AM - rmfischer - Z:\Clients\TND\NUSC\129460\_MWSSSTBridge\Design\Underground\PG23\_Bridge\_Plan\_Sheet\_3.dwg - North 1  
 NU VER: BUR\_VER



**NOTES:**  
 SEE PG25 FOR DUCT BANK PROFILE ACROSS BRIDGES.

ALL MAIN BRIDGE UTILITY SUPPORTS SHALL BE TYPE S1, EXCEPT FOR LOCATIONS MARKED S2, S3, S4, OR S5. LOCATIONS MARKED S5 SHALL BE ANCHOR HANGERS. SEE PG30 FOR DETAILS.

"E##" CORRESPONDS TO DUCTBANK EXPANSION JOINT NUMBER ##. SEE PG26 FOR DETAILS.


INSTALL HANGER FRAMES ON MAIN BRIDGE UTILITY SUPPORTS AND CROSS FRAMES. PER MAIN BRIDGE PLANS, MAX SPACING BETWEEN UTILITY SUPPORTS AND/OR CROSS FRAMES = 9'-6".

SEE PROPOSED MAIN BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR FRAMING DETAILS, INCLUDING LOCATION OF UTILITY SUPPORTS AND CROSS FRAMES.

CROSS FRAMES AND UTILITY SUPPORTS ARE ONLY SHOWN IN BAY OF PROPOSED DUCTBANK, FOR CLARITY.

CENTERLINES OF BOX GIRDER WEBS ARE SHOWN AT TOP OF WEB.

STATIONING ALONG BASELINE OF BRIDGE SHOWN FOR INFORMATION ONLY, SEE BRIDGE PLANS



This document has been digitally sealed.  
07/02/2021



**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER  
 designed A. FERDON checked J. DAVIS

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**


TITLE: NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT BRIDGE PLAN SHEET 3 OF 4 BOSTON, MASSACHUSETTS

BY: A. FERDON - BMcD	CHKD: J.DAVIS - BMcD	APP: -	APP: -
DATE: 07/02/21	DATE: -	DATE: -	DATE: -
H-SCALE: 1" = 12'	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.: -	R.E. DWG	
R.E. PROJ. NUMBER		NUSC0	

PG23




7/2/2021 11:00 AM - nrfischer - Z:\Clients\IND\NUSC\129460\_MWNSSTBridge\Design\Underground\CADD\Bridges\Plan\_Sheet\_4.dwg - North 1



TO SOUTH PLAN & PROFILE  
(SEE DWG PG05)  
N: 2,959,228.03  
E: 775,393.11  
ELEVATION: 13.47

MATCHLINE STA. 25+79.40 SEE PG23

- NOTES:**
- SEE PG25 FOR DUCT BANK PROFILE ACROSS BRIDGES.
  - ALL MAIN BRIDGE UTILITY SUPPORTS SHALL BE TYPE S1, EXCEPT FOR LOCATIONS MARKED S2, S3, S4, OR S5. LOCATIONS MARKED S5 SHALL BE ANCHOR HANGERS. SEE PG30 FOR DETAILS.
  - "E##" CORRESPONDS TO DUCTBANK EXPANSION JOINT ##. SEE PG26 FOR DETAILS.
  - INSTALL HANGER FRAMES ON MAIN BRIDGE UTILITY SUPPORTS AND CROSS FRAMES. PER MAIN BRIDGE PLANS, MAX SPACING BETWEEN UTILITY SUPPORTS AND/OR CROSS FRAMES = 9'-6"
  - SEE PROPOSED MAIN BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR FRAMING DETAILS, INCLUDING LOCATIONS OF UTILITY SUPPORTS AND CROSS FRAMES.
  - CROSS FRAMES AND UTILITY SUPPORTS ARE ONLY SHOWN IN BAY OF PROPOSED DUCTBANK, FOR CLARITY.
  - CENTERLINES OF BOX GIRDER WEBS ARE SHOWN AT TOP OF WEB.
  - STATIONING ALONG BASELINE OF BRIDGES SHOWN FOR INFORMATION ONLY, SEE BRIDGE PLANS



This document has been digitally sealed.  
07/02/2021



**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER  
designed A. FERDON checked J. DAVIS

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

# EVERSOURCE ENERGY


NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE PLAN SHEET 4 OF 4  
BOSTON, MASSACHUSETTS

DATE	DATE	DATE	DATE	DATE
07/02/21	-	-	-	-

FIELD BOOK & PAGES  
R.E. DWG  
NUSC




DUCTBANK PROFILE ACROSS BRIDGES



DUCTBANK PROFILE ACROSS BRIDGES

NOTES:  
ALL ELEVATIONS ARE REFERENCED TO THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 88).



This document has been digitally sealed. 07/02/2021

**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021

designed A. FERDON

detailed N. FISCHER

checked J. DAVIS


NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-

NO.	DATE	AS-BUILT REVISIONS	BY	CHK	APP	APP

**EVERSOURCE ENERGY**

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE PROFILE SHEET  
BOSTON, MASSACHUSETTS

BY: A. FERDON - BMcD	CHKD: J.DAVIS - BMcD	APP: -	APP: -
DATE: 07/02/21	DATE: -	DATE: -	DATE: -
H-SCALE: 1" = 25'	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: 1" = 5'	V.S.: -	R.E. DWG	
R.E. PROJ. NUMBER	NUSCO		PG25




**INTERMEDIATE DIAPHRAGM TYPICAL SECTION**  
FACING NORTH. NOT TO SCALE

SEE PG 27 FOR DIAPHRAGM HOLE SIZE DIMENSIONS.


SEE BRIDGE PLAN SHEETS FOR LOCATION OF DIAPHRAGMS "D###". DIMENSION "X" IS MEASURED ALONG THE CENTERLINE OF THE INTERMEDIATE DIAPHRAGM.

DIMENSIONS FOR NEW W30x99 INTERMEDIATE DIAPHRAGM TO BE DETERMINED BY CONTRACTOR USING EXISTING WAREHOUSE BRIDGE PLANS AND FIELD MEASUREMENTS.




ELEVATION A-A


INTERMEDIATE DIAPHRAGM	DIMENSION "X"
D01	3'-11 3/8"
D02	3'-10 5/16"
D03	3'-9 1/4"
D04	3'-10 13/16"
D05	3'-4 1/8"
D06	3'-8 1/8"
D07	3'-0 13/16"
D08	3'-6 13/16"
D09	2'-10 1/2"
D10	4'-3 13/16"
D11	3'-9 3/8"
D12	3'-8 9/16"
D13	4'-0 7/8"




HANGER FRAME 2 IS SIMILAR TO HANGER FRAME 1, EXCEPT FOR ALTERNATE BAR AND TUBE ARRANGEMENT, AS SHOWN.




HANGER FRAME 3 IS IDENTICAL TO HANGER FRAME 2, EXCEPT FOR ALTERNATE BAR AND TUBE ARRANGEMENT AS SHOWN




HANGER FRAME 4




**WAREHOUSE UTILITY SUPPORT DETAIL - TYPE 1**  
FACING NORTH. NOT TO SCALE




**WAREHOUSE UTILITY SUPPORT DETAIL - TYPE 2**  
FACING NORTH. NOT TO SCALE




ELEVATION B-B



**STIFFENER PLATE DETAIL**  
NOT TO SCALE



ELEVATION C-C



This document has been digitally sealed. 07/02/2021

**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-

<b>BURNS MEDONNELL</b>	
date	JULY 2, 2021
designed	A. FERDON
detailed	N. FISCHER
checked	J. DAVIS

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE DETAIL SHEET 1 OF 5  
BOSTON, MASSACHUSETTS

DATE	07/02/21	DATE		DATE	
H-SCALE	N/A	SIZE	D	FIELD BOOK & PAGES	
V-SCALE	N/A	V.S.		RE. DWG	
R.E. PROJ. NUMBER				REVISION	

PG26

**NOTES:**  
SEE EXISTING WAREHOUSE BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR INFORMATION ON EXISTING BEAMS, BEARINGS, PIERS, AND ELEVATIONS. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN FIELD PRIOR TO ORDERING NEW MATERIAL.

ALL CONDUITS SHALL BE EXTRA HEAVY WALL FIBERGLASS ("BULLET RESISTANT"). HANGER ASSEMBLIES SHALL CONSIST OF FIBERGLASS SQUARE TUBES (2" x2" x3/4"). ROUND TUBES (THREADED ROD SLEEVES, 1" DIA.), AND 3/4" DIA. GALVANIZED STEEL THREADED RODS, NUTS, WASHERS, AND LOCK WASHERS. CONDUITS AND HANGER ASSEMBLIES SHALL BE CHAMPION FIBERGLASS, OR ENGINEER APPROVED EQUIVALENT.

THREADED ROD, HEX NUTS, FLAT WASHERS, AND LOCK WASHERS SHALL CONFORM TO ASTM A307 AND SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A153. THREADED ROD SHALL HAVE A MINIMUM TENSILE STRENGTH OF 74,000 PSI.

ALL STRUCTURAL STEEL SHALL CONFORM TO ASTM A709 GRADE 50 AND SHALL BE GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123.


HIGH STRENGTH BOLTS SHALL CONFORM TO A325. BOLTS, NUTS, AND WASHERS SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM A153.

STRUCTURAL STEEL WAREHOUSE UTILITY SUPPORTS SHALL BE FASTENED TO THE EXISTING CONCRETE DECK WITH HILTI KWIK BOLT T2 EXPANSION ANCHORS AS SHOWN IN THE DETAILS. EXPANSION ANCHORS SHALL BE STAINLESS STEEL, TYPE 316. INSTALL A SACRIFICIAL ANCHOR WITHIN 12" OF EACH PROPOSED CONDUIT SUPPORT LOCATION, PRIOR TO INSTALLING ANCHORS FOR CONDUIT HANGERS. CONSULT HILTI FOR MINIMUM ANCHOR EMBEDMENT AND TORQUE REQUIREMENTS IN 4000 PSI CONCRETE. A HILTI REPRESENTATIVE SHALL TEST PULL EACH OF THE SACRIFICIAL ANCHORS FOR A MINIMUM SAFE WORKING PULLOUT CAPACITY OF 2,000 LBS. PER ANCHOR. NOTIFY THE ENGINEER IF ANY SACRIFICIAL ANCHORS FAIL THE PULLOUT TEST. ONCE ALL PULLOUT TESTS ARE SUCCESSFULLY COMPLETED, THE CONDUIT SUPPORT ANCHORS CAN BE INSTALLED. CONTRACTOR SHALL PROVIDE THE ENGINEER WITH WRITTEN VERIFICATION OF ANCHOR PULLOUT TEST RESULTS WITHIN 5 DAYS AFTER TESTS ARE COMPLETED.

CONTRACTOR SHALL VERIFY ALL PHASE CONDUITS PASS THROUGH SINGLE HOLE IN STEEL DIAPHRAGM OR CONCRETE BACKWALL.

\*FOR HANGER FRAME 3, CUT FIBERGLASS SLEEVES IN FIELD TO ACHIEVE ADEQUATE OPENING FOR SLOPED CONDUIT. SEE DETAIL R.

SPLIT HP16x101 SECTIONS SHALL BE SPLIT IN SHOP TO THE DEPTH SHOWN.




CONDUIT EXPANSION JOINTS TO BE LOCATED IN THE BAYS SHOWN ON BRIDGE PLAN SHEETS, AT LOCATIONS "E##".

CONTRACTOR TO SELECT EXPANSION JOINT LOCATION WITHIN BAY SUBJECT TO CONSTRAINTS SHOWN IN DETAIL U.


SEE PG29 AND PG30 FOR DETAILS OF ANCHOR SUPPORTS.

EXPANSION JOINT LOCATION	MINIMUM STROKE
E01	4"
E02	4"
E03	4"
E04	4"
E05	14"
E06	6"
E07	6"
E08	6"
E09	6"
E10	6"
E11	6"




**WAREHOUSE ABUTMENT BACKWALL SECTION A**  
LOOKING NORTH. NOT TO SCALE


CUT HOLE IN BACKWALL. HOLE SIZE 2. LOCATE HOLE TO ALIGN WITH HOLE IN NEW END DIAPHRAGM. CUT APPROACH SLAB AS NEEDED.  
AFTER CONDUIT INSTALLATION IS COMPLETE, FILL HOLE IN BACKWALL WITH NON-SHRINKING GROUT, TYP.




**PIER A6 NORTH END DIAPHRAGM SECTION E**  
LOOKING NORTH. NOT TO SCALE




**PIER A5 NORTH END DIAPHRAGM SECTION G**  
LOOKING NORTH. NOT TO SCALE




**WAREHOUSE ABUTMENT END DIAPHRAGM SECTION B**  
LOOKING NORTH. NOT TO SCALE




**PIER A6 SOUTH END DIAPHRAGM SECTION F**  
LOOKING NORTH. NOT TO SCALE



**PIER A5 SOUTH END DIAPHRAGM SECTION H**  
LOOKING NORTH. NOT TO SCALE



**WAREHOUSE ABUTMENT ELEVATION X**  
LOOKING WEST. NOT TO SCALE



HOLE SIZE	DIM. "A"	DIM. "B"	DIM. "C"	DIM. "D"
1	3'-9"	1'-11"	1'-4 1/2"	6"
2	3'-9"	1'-10"	1'-4 1/2"	5"
3	3'-9"	2'-2"	1'-4 1/2"	VARIES
4	3'-9"	2'-3"	1'-4 1/2"	6"

**NOTES:**  
SEE EXISTING WAREHOUSE BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR INFORMATION ON EXISTING BEAMS, BEARINGS, PIERS, AND ELEVATIONS.

DIMENSIONS AND ELEVATIONS ARE BASED ON EXISTING WAREHOUSE BRIDGE PLANS AND PROPOSED MAIN BRIDGE PLANS. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN FIELD BEFORE ORDERING NEW MATERIAL.

SEE PG26 FOR HANGER FRAME DETAILS, AND SPECIFICATIONS, AND STRUCTURAL STEEL SPECIFICATIONS.



This document has been digitally sealed. 07/02/2021

**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER  
designed A. FERDON checked J. DAVIS









NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE DETAIL SHEET 2 OF 5  
BOSTON, MASSACHUSETTS

DATE	DATE	DATE	DATE
07/02/21	-	-	-



NOTES:  
DIMENSIONS AND ELEVATIONS ARE BASED ON EXISTING WAREHOUSE BRIDGE PLANS AND PROPOSED MAIN BRIDGE PLANS. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN FIELD BEFORE ORDERING NEW MATERIAL

SEE EXISTING WAREHOUSE BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR INFORMATION ON EXISTING BEAMS, BEARINGS, PIERS, AND ELEVATIONS.

SEE PG26 FOR HANGER FRAME DETAILS AND SPECIFICATIONS, AND STRUCTURAL STEEL SPECIFICATIONS.

SEE PG26 FOR HOLE SIZE DIMENSIONS.



This document has been digitally sealed. 07/02/2021

**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER

designed A. FERDON checked J. DAVIS

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-



NO.	DATE	AS-BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**






NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE DETAIL SHEET 3 OF 5  
BOSTON, MASSACHUSETTS

DATE	DATE	DATE	DATE
07/02/21	-	-	-

H-SCALE N/A V-SCALE N/A  
R.E. DWG N/A  
R.E. PROJ. NUMBER N/A



ABUTMENT	PROPOSED BRIDGE BEARING SEAT ELEV.	"A"	"B"	"C"
NORTH	19.92	2'-4 1/4"	1'-4 1/4"	1'-5 1/2"
SOUTH	11.33	2'-2 7/16"	1'-2 7/16"	1'-1 11/16"



\*EXAMPLE 3D VIEW IS SHOWN FOR REFERENCE ONLY. HANGER FRAME CONFIGURATIONS SHALL BE AS SHOWN IN THESE PLANS.

SPLIT ANCHOR RINGS, ADJUSTABLE BRACKETS, AND THREADED RODS FOR ANCHOR SUPPORTS SHALL BE SUPPLIED BY CHAMPION FIBERGLASS, OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ANCHOR SUPPORTS TO ENGINEER FOR APPROVAL.

SPLIT ANCHOR RINGS SHALL BE BONDED WITH EPOXY RESIN TO CONDUITS, IN ACCORDANCE WITH MANUFACTURER SPECIFICATIONS.

**NOTES:**  
SEE PROPOSED MAIN BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR INFORMATION ON BOX GIRDERS, UTILITY SUPPORTS, CROSS FRAMES, BEARINGS, PIERS, AND ELEVATIONS. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN FIELD PRIOR TO ORDERING NEW MATERIAL.



This document has been digitally sealed. 07/02/2021



129460

date JULY 2, 2021  
designed A. FERDON  
detailed N. FISCHER  
checked J. DAVIS

**ISSUED FOR CONSTRUCTION**


NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-


**EVERSOURCE ENERGY**

NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE DETAIL SHEET 4 OF 5  
BOSTON, MASSACHUSETTS

DATE	DATE	DATE	DATE
07/02/21	N/A	N/A	-




**MAIN BRIDGE CROSS FRAME UTILITY SUPPORT SECTION T**  
FACING NORTH. NOT TO SCALE.




**MAIN BRIDGE TYPE S1 UTILITY SUPPORT SECTION S1**  
FACING NORTH. NOT TO SCALE.

ALL UTILITY SUPPORTS ON MAIN BRIDGE USE TYPE S1, EXCEPT FOR LOCATIONS NEAR THE NORTH AND SOUTH ABUTMENTS MARKED S2, S3, OR S4. SEE BRIDGE PLAN SHEETS FOR LOCATIONS.




**MAIN BRIDGE TYPE S2 UTILITY SUPPORT SECTION S2**  
FACING NORTH. NOT TO SCALE.

TYPE S2 IS IDENTICAL TO S1, EXCEPT FOR REVISED CONDUIT, BAR, AND TUBE CONFIGURATION SHOWN IN HANGER FRAME 5.




**MAIN BRIDGE TYPE S3 UTILITY SUPPORT SECTION S3**  
FACING NORTH. NOT TO SCALE.

TYPE S3 IS IDENTICAL TO S1, EXCEPT FOR REVISED CONDUIT, BAR, AND TUBE CONFIGURATION SHOWN IN HANGER FRAME 6.



**MAIN BRIDGE TYPE S4 UTILITY SUPPORT SECTION S4**  
FACING NORTH. NOT TO SCALE.

TYPE S4 IS IDENTICAL TO S1, EXCEPT FOR REVISED CONDUIT, BAR, AND TUBE CONFIGURATION SHOWN IN HANGER FRAME 7.




**MAIN BRIDGE TYPE S5 UTILITY ANCHOR SUPPORT PROFILE Z**  
NOT TO SCALE.

SPLIT ANCHOR RINGS, ADJUSTABLE BRACKETS, AND THREADED RODS FOR ANCHOR SUPPORTS SHALL BE SUPPLIED BY CHAMPION FIBERGLASS, OR ENGINEER APPROVED EQUIVALENT. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ANCHOR SUPPORTS TO ENGINEER FOR APPROVAL.

SPLIT ANCHOR RINGS SHALL BE BONDED WITH EPOXY RESIN TO CONDUITS, IN ACCORDANCE WITH MANUFACTURER SPECIFICATIONS.

**NOTES:**  
SEE PROPOSED MAIN BRIDGE PLANS IN SPECIFICATION SECTION 337119.34 FOR INFORMATION ON BOX GIRDERS, UTILITY SUPPORTS, CROSS FRAMES, BEARINGS, PIERS, AND ELEVATIONS. CONTRACTOR SHALL VERIFY ALL DIMENSIONS IN FIELD PRIOR TO ORDERING NEW MATERIAL.



**MAIN BRIDGE TYPE S5 UTILITY ANCHOR SUPPORT SECTION S5**  
FACING NORTH. NOT TO SCALE.

TYPE S5 IS SIMILAR TO S1, EXCEPT FOR ADDITION OF ANCHOR BRACKETS & RODS AND REVISED BAR AND TUBE CONFIGURATION SHOWN IN HANGER FRAME 8.



This document has been digitally sealed. 07/02/2021

**ISSUED FOR CONSTRUCTION**



129460

date JULY 2, 2021 detailed N. FISCHER  
designed A. FERDON checked J. DAVIS

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	07/02/21	ISSUED FOR CONSTRUCTION	ASF	JMD	-	-


NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

**EVERSOURCE ENERGY**



NORTH WASHINGTON STREET  
BRIDGE CABLE REPLACEMENT  
BRIDGE DETAIL SHEET 5 OF 5  
BOSTON, MASSACHUSETTS

DATE	DATE	DATE	DATE
07/02/21	-	-	-

7/1/2021 1:29 PM - j.schatz - \\pmsd\vis\clients\IND\NISC\129460\_WashStBridge\_Design\Underground\CADD\Working\REMOVAL\_PLAN.dwg - Sheet Layout



- NOTES:**
- OIL TO BE REMOVED FROM FREEZE PIT. EXISTING CABLE TO REMAIN IN PLACE AND TO BE REUSED. EXISTING STEEL PIPE TO BE REMOVED, AS REQUIRED TO ACCOMMODATE NEW HPFF STEEL PIPE.



*Signature*  
**COMMONWEALTH OF MASSACHUSETTS**  
**LANE PATRICK PULS**  
**CIVIL**  
**No. 48318**  
**REGISTERED**  
**PROFESSIONAL ENGINEER**  
*7-2-2021*



**ISSUED FOR CONSTRUCTION**

NO.	DATE	DESIGN REVISIONS	BY	CHK	APP	APP
0	7/2/21	ISSUED FOR CONSTRUCTION	JAS	MJD	-	-

<b>BURNS &amp; MCDONNELL</b>	
129460	
date	detailed
JAN. 22, 2021	J. SCHATZ
designed	checked
M.DAGENAIS	N.SCOTT

NO.	DATE	AS BUILT REVISIONS	BY	CHK	APP	APP
-	-	-	-	-	-	-

# EVERSOURCE ENERGY

**NORTH WASHINGTON STREET BRIDGE CABLE REPLACEMENT REMOVAL PLAN**  
 BOSTON, MASSACHUSETTS

BY: J. SCHATZ - BMcD	CHK: M. DAGENAIS - BMcD	APP: N. SCOTT - BMcD	APP: -
DATE	DATE	DATE	DATE
H-SCALE: 1" = 80'	SIZE: D	FIELD BOOK & PAGES	
V-SCALE: N/A	V.S.	R.E. DWG	
REF. PROJ. NUMBER	NISC0		PG31