

ITEM 508.4

SLOPE TO VERTICAL GRANITE  
TRANSITION CURB

EACH

GENERAL

Work under this item shall conform to the relevant provisions of Section 501 of the MassDOT Standard Specifications and the following:

MATERIALS

All curb to be set shall be placed on cement concrete base over a crushed stone in accordance with the Plans and specifications for Item 156.12, Crushed Stone for Curb Foundation.

All granite curbing shall be in conformance with Subsection M9.04 of the MassDOT Standard Specifications and the details on the Plans.

CONSTRUCTION METHODS

Prior to setting the curb, the curb shall be cleaned of all debris.

The Contractor shall excavate a sufficient area in depth and width in order to install the curb on a cement concrete base over a crushed stone base in accordance with the Plans. The Contractor shall set the curb on the cement concrete foundation prior to the installation of the new roadway material. The granite curbing shall be installed in conformance with the construction drawings.

METHOD OF MEASUREMENT

Slope to Vertical Granite Transition Curb will be measured for payment per each, complete in place.

BASIS OF PAYMENT

Slope to Vertical Granite Transition Curb will be paid for at the Contract unit price per each, which price shall include all labor, materials, equipment, and incidental costs required to complete the work. No separate payment will be made for the cement concrete base, but all costs in connection therewith shall be included in the Contract unit price bid.

Crushed stone will be paid for separately under Item 156.12, Crushed Stone for Curb Foundation.