

ITEM 874.2

TRAFFIC SIGNS REMOVED AND RESET

EACH

Work under this item shall conform to the relevant provisions and amendments of the MassDOT "Standard Specifications for Highways and Bridges", Section 840 and the following:

Any sign scheduled to be removed and reset, regardless of type or size, will be included in this item, unless specifically designated for inclusion under another item. Any additional hardware (bolts, nuts, washers, brackets, etc.) necessary to install the specified signs at the designated locations on new or existing posts will be supplied under this item. This includes the removal and disposal of the existing sign support foundations and the backfilling of resulting holes with necessary material as approved by the Engineer.

Payment for this Item will be made at the contract unit price bid each, which price and payment will be full compensation for all labor, tools, equipment, material, including and additional mounting hardware, transportation, and all incidental expenses necessary to complete this item to the satisfaction of the Engineer.

Where new posts are required, payment will be made under Item 877.3 Sign Post 2-inch Steel or Item 877.4 Sign Post 2-1/2 inch Steel, unless otherwise specified.